No.	Items of work	Unit	Quantity	Rate	Rate in Figures	Rate in Words
				Rs. a. p.		
	SLUICE.					
1	Earthwork cut opening the bund ..	C.yd.	60	0 3 0		
2	Removing and resetting stone revetment with new jelly	,,	7	0 12 0		
3	Stone jelly concrete in surki mortar ..	C.ft.	106	0 4 6		
4	Burnt brick in surki mortar ..	,,	193	0 4 9		
5	Plastering with surki mortar ..	Sqr.	2·10	3 8 0		
6	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	66	0 6 0		
7	Cutting orifice in slabs	Each	4	0 12 0		
8	Fixing C.I. pipes 6″ Dr. including conveying from Divisional Office, laying, etc., complete (Pipes supplied Departmentally)	R.ft.	27	3 0 0		
9	Refilling the earth got from cut opening the bund and consolidating ..	C.yd.	60	0 2 0		
10	Providing and fixing wooden plug with locking arrangements, etc., complete	Each	1	15 0 0		
11	Rough stone work new	C.yd	3	1 10 0		
	"WASTE WEIR"					
1	Earthwork excavation, forming bank with consolidation	C.yd.	87	0 3 6		
2	Burnt brick in surki mortar ..	C.ft.	226	0 4 9		
3	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft	111	0 6 0		
4	Joggle joints	Each	10	0 12 0		
5	Plastering with surki mortar ..	Sqr.	3·37	3 8 0		
6	Rough stone work new	C.yd.	25	1 10 0		

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

REVISED TENDER NOTICE FORMS.

Notification dated 9th April 1936.

Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 11 A.M. on 9th May 1936.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, on payment of Rupee one for each form should be addressed to the Executive Engineer, Kolar Division, and should be superscribed as "Tender for Restoring Breached Naravalapalli Dadinavaddu, Register No. 783, Bagepalli Taluk". The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 300 (Rupees three hundred) in cash or Government Promissory Notes of Mysore Government bonds at face value or market value whichever is less as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract (cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers, who wish to be present on 9th May 1936. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the works in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas, and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities given in the schedule are only approximate and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

16. The works should be completed and handed over to the Public Works Department by the end of the month to be fixed by the Executive Engineer, failing which the Executive Engineer may at his discretion levy a penalty of Rs..... per day which will be recoverd from the Contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

18. The earnest money on rejected tenders will be returned on submission of the receipt originally granted along with an application to the Executive Engineer.

19. No claim for damages for delays caused by Officers of the Department in the execution of work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the Departmental Officers will however be considered on the merits of each case.

20. The contract should not be sub-let.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderers will pay the hire, etc., on machinery at 18 to 25 per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the stores to the date of return to the stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tools.

Note.—(*a*) The Contractor should at his own cost:

(1) provide rods, stakes, ropes and labourers required in setting out the works,
(2) provide all necessary scaffolding, centering, labour and appliance for hoisting,
(3) provide mortar mill and shed to keep materials under cover and also for workmen,
(4) arrange for protecting work during inclement weather,
(5) supply requisite temporary lights, water cisterns, water shoots, coverings to masonry tile pieces to steps, sieves parsha or measures, shoring and other requisite protection during the progress of the work,
(6) supply all water required for work and workmen and shall provide latrines, drainages, etc.,
(7) clean away all dirt, rubbish, superfluous materials and debris as they accumulate,
(8) provide arrangements for pumping and baling from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.,
(9) wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, and
(10) afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note (*b*).—It is the business of the Contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for restoring the breached Naravalapalli Dadinavoddu, Register No. 783, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. BUND AT R.L. 55.00. TOP WIDTH 4½' SLOPE 2 : 1 AND 1½ : 1.		Rs. a. p.		
1	Clearing jungle including roots	Grades	1 0 0	15	
2	Cutting grips and trenches for the receipt of new earth	,,	1 8 0	15	
3	Cleaning loose earth from scours	L.S.			
4	Earthwork to bund with watering and consolidation	C.yd.	0 3 6	6,449	
5	Lead for the earth got from draft and approach clearing including watering and consolidation	,,	0 1 6	1,278	
6	Turfing the slopes of bund	S.yd.	0 0 9	4,519	
7	Closing the leak and filling a big hole in bund of 6'×12'	L. S.			
8	Rough stone work new as per statement ..	C.yd.	1 8 0	194	
9	Removing and resetting old stone work with new jelly	,,	0 8 0	100	
10	Providing and fixing new grade stones including figuring and painting, etc., complete ..	Each	1 8 0	10	
11	Removing and refixing old grade stones including, figuring, painting, etc., complete ..	,,	0 8 0	5	
12	Do Index stones do ..	,,	0 4 0	5	
13	Providing and fixing new Index Stones including figuring, painting, etc., complete ..	,,	0 8 0	10	
14	Providing and fixing new Register No. and Date stones, including figuring, painting, etc., complete	Each	3 8 0	1	
15	Do B.M. stones do ..	,,	2 8 0	2	
16	Do Gauge stone do ..	,,	15 0 0	1	
	II. BREACH FILLING.				
1	Clearing site and debris and bailing water in breach	L. S.			
2	Cutting vertical grooves to sides of old bund and using the same to rear of bund ..	C.yd.	0 3 0	217	
3	Clearing silt in breaches	,,	0 3 0	1,741	
4	Earthwork excavation for foundation of Puddle wall	,,	0 3 6	44	
5	Puddle wall	,,	0 10 0	226	
6	Earthwork to breach with mixture of 50 per cent of clay and gravel including watering and consolidation	,,	0 6 0	4,215	
7	Gravel backing behind revetment	,,	0 10 0	229	
8	Rough stone work new for revetment ..	,,	1 8 0	305	
9	Turfing the slopes	S.yd.	0 0 9	627	
	III. SLUICE.				
1	Sundry repairs to sluice and providing plug and rod with locking arrangements ..	L. S.			
	IV. EXTENDING LEFT WASTE WEIR 48 FT. LONG BY 102 FT. LONG TOWARDS LEFT. (TOTAL 150 FT. AT R.L. 50 : 00).				
1	Clearing draft and approach and using the same to rear of bund (Gravelly soil) ..	C.yd.	0 4 0	1,917	
2	Earthwork excavation for foundation ..	,,	0 4 0	19	
3	Dry stone for body wall	,,	1 8 0	19	

N. SUBBA RAO,
Executive Engineer.